



Equipment Type & Description: Type DER Drum Rotators Sheet: 1 of 9

Operation	Hazards Identified	Risk Assessment	Risk Control Measures in Place	Risk Control In Place (Date)
Industrial Truck Operational Safety Pre-Checks.	a) Unsafe use of Industrial Truck resulting in Attachment /Drum shifting, falling and striking Pedestrians and/or objects.	 Serious Risk to Operator. Serious Risk to Pedestrians. 	 Pre-operational inspections (in accordance with AS 2359.2), to be carried out before each shift Industrial Truck taken out of service if any risks or malfunctions are found. These MUST be reported & recorded for assessment by a competent person. The operational areas to be assessed for hazards prior to and during work shifts. The Industrial Truck to be left in a safe condition after each shift. Inspections, maintenance and repairs to be carried out in accordance with the relative Industrial Truck Operating Manuals and AS 2359.2. If more than 25 persons employed at workplace/site, a Certified First Aider to be at Workplace or on Site. 	

Assessment carried out by: Ben PRASAD, East West Engineering Date of Assessment: 24th February, 2015





Equipment Type & Description: Type DER Drum Rotators Sheet: 2 of 9

	Operation	Hazards Identified		Risk Assessment		Risk Control Measures in Place	Risk Control In Place (Date)
2.	Attachment Operational Safety Pre-Checks.	a) Attachment /Drum shifting, falling and striking Pedestrians and/or objects.	•	Serious Risk to Pedestrians. Moderate Risk to Operator.	-	Inspections, maintenance and repairs to be carried out in accordance with Instruction Manual. All Pre-Checks listed in the Instruction Manual and Options Manual are to be carried out before each shift. The safety chain, Belly Strap & locking lynch pin must be checked daily. The attachment is to be fitted securely to the lifting apparatus with the safety chain installed, according to the Instruction Manual. All instructions for the use of the attachment as laid out in the Instruction Manual and Options Manual are to be followed. The use of the attachment is limited to those situations for which it is specifically designed and in accordance with AS 2359.1 where applicable.	

Assessment carried out by: ______ Ben PRASAD, East West Engineering _____ Date of Assessment: _____ 24th February, 2015





Equipment Type & Description: Type DER Drum Rotators Sheet: 3 of 9

Operation	Hazards Identified	Risk Assessment	Risk Control Measures in Place	Risk Control In Place (Date)
3. Lifting & lowering Attachment and Drum.	a) Unsafe/Incompetent Operator.	 Serious Risk to Operator. Serious Risk to Pedestrians. 	 Only Certified & fully Trained Operators are to use equipment The Industrial Truck to be operated in accordance with AS 2359.2 section (3) and these Instructions. 	
	b) Items Falling from Height.	 Serious Risk to Pedestrians. Moderate Risk to Operator. 	 All Risk Control Measures outlined in 2(a) above are to be in place. Barriers /warning Signs in areas subject to passing traffic to be installed. The Working Load Limit of the Rotator is not to be exceeded. Drums are not to be lifted unless they are in good condition. The Drum is NOT to be dragged or pushed along the ground with the attachment. The Operator to ensure the Drum is secured inside the drum cradle in accordance with these Instructions. (continued on sheet 4 of 9) 	

	Assessment carried out by:	Ben PRASAD, East West Engineering	Date of Assessment:	24 th February, 2	.015
--	----------------------------	-----------------------------------	---------------------	------------------------------	------





Equipment Type & Description: Type DER Drum Rotators Sheet: 4 of 9

Operation	Hazards Identified	Risk Assessment	Risk Control Measures in Place	Risk Control In Place (Date)
3. Lifting & lowering Attachment and Drum. (continued)	b) Items Falling from Height. (continued)	 Serious Risk to Pedestrians. Moderate Risk to Operator. 	 Avoid lifting drums that are "Out of Shape". The attachment /Drum to be raised no higher than necessary. The Industrial Truck mast, if adjustable, to be back tilted. 	(=)
	c) Load too heavy and/or unbalanced – Industrial Truck overturning.	 Serious Risk to Pedestrians. Serious Risk to Operator. 	 All Risk Control Measures outlined in 3(b) above are to be in place. The Operator to be aware of the weight of attachment & Drum. Operator to gain assurance from a responsible person that the Drum may be handled safely. The rating capacity of the Industrial Truck to handle the load is NOT to be exceeded. The Industrial Truck to be used only on a hard level surface, the area assessed before usage. The attachment to be raised unladen to working height to confirm all systems are functioning. 	

Assessment carried out by: <u>Ben PRASAD, East West Engineering</u> Date of Assessment: <u>24th February, 2015</u>





Equipment Type & Description: Type DER Drum Rotators Sheet: 5 of 9

Operation	Hazards Identified	Risk Assessment	Risk Control Measures in Place	Risk Control In Place (Date)
3. Lifting & lowering Attachment and Drum. (continued)	d) Industrial Truck /Attachment /Drum striking Pedestrians.	Serious Risk to Pedestrians.	 All Risk Control Measures outlined in 3(b) above are to be in place. A suitable clear space between barriers to be left to safely use the attachment. 	
	e) Industrial Truck Mast striking overhead fittings.	 Serious Risk to Operator. Serious Risk to Pedestrians. 	 Work areas to be assessed to ensure NO overhead fittings can be contacted by mast, attachment, or load. Industrial Truck to keep clear of any overhead obstructions especially ELECTRICAL conductors. 	

Assessment carried out by:	Ben PRASAD, East West Engineering	Date of Assessment:	24 th February,	2015

Risk Control Measures & Risk Assessment for Identified Hazards



Equipment Type & Description: Type DER Drum Rotators Sheet: 6 of 9

	Operation	Hazards Identified		Risk Assessment		Risk Control Measures in Place	Risk Control In Place (Date)
4.	Rotating Drums using the Attachment's Handle or Chain (depending on Model).	a) Drum Shifting/Falling.	•	Serious Risk to Operator. Serious Risk to Pedestrians.	-	All Risk Control Measures outlined in Section (3) above are to be in place. The Operator to ensure the Drum is secured inside the drum cradle in accordance with the Instruction Manual.	
		b) Attachment /Drum striking Operator or Pedestrians.	•	Serious Risk to Operator. Serious Risk to Pedestrians.	-	All Risk Control Measures outlined in 4(a) above are to be in place. Hands to be kept away from the Hand Chain Wheel & Guide during operation. The Operator to keep the Gearbox Chain or Handle under control at all times during rotation to prevent possible over-runs. The Operator to replace the Chain into the Chain Bucket after rotation and prior to transportation.	

Assessment carried out by: <u>Ben PRASAD, East West Engineering</u> Date of Assessment: <u>24th February, 2015</u>





Equipment Type & Description: Type DER Drum Rotators Sheet: 7 of 9

Operation	Hazards Identified	Risk Assessment	Risk Control Measures in Place	Risk Control In Place (Date)
5. Transporting loads with Attachment about the Workplace or Site.	a) Load Shifting/Falling. b) Industrial Truck /Attachment striking Pedestrians.	 Serious Risk to Pedestrians. Moderate Risk to Operator. Serious Risk to Pedestrians. 	 All Risk Control Measures outlined in 3(b) and 3(c) above are to be in place. The Operator to check the drum is secured to the attachment in accordance with the Instruction Manual. The Drum to be transported no higher than necessary. All Risk Control Measures outlined in 3(d) above are to be in place. A system is to be developed for handling the Loads about the Workplace/Site. Convex mirrors are to be placed at Aisle corners in areas used by Industrial Trucks. All safety equipment on the Industrial Truck MUST be functioning before use, (ie Reversing Beepers). Manoeuvre slowly & cautiously when Loads are elevated. 	

Assessment carried out by: _____ Ben PRASAD, East West Engineering ____ Date of Assessment: ____ 24th February, 2015





Equipment Type & Description: Type DER Drum Rotators Sheet: 8 of 9

	Operation	Hazards Identified		Risk Assessment		Risk Control Measures in Place	Risk Control In Place (Date)
5.	Transporting loads with Attachment about the Workplace or Site. (continued)	c) Operator exposed to fixed/moving components.	•	Serious Risk to Operator.	-	The Operator is to stay with the Industrial Truck controls at all times whilst in operation. The Operator is to keep hands/feet wholly within Industrial Truck cab whilst in operation. The Operator to replace the Chain into the Chain Bucket after rotation and prior to transportation.	
		d) Industrial Truck /Attachment striking obstacles.	•	Serious Risk to Operator.	-	All Risk Control Measures outlined in 3(e), 4(b) and 4(c) above are to be in place.	
		e) Industrial Truck /Attachment falling from raised areas.	•	Serious Risk to Operator. Serious Risk to Pedestrians.	-	All Risk Control Measures outlined in 4(b) and 4(c) above are to be in place. All safety railings are to be placed in raised areas such as Ramps, Loading Docks etc.	

Assessment carried out by:	Ben PRASAD, East West Engineering	Date of Assessment:	24 th February, 2015





Equipment Type & Description: Type DER Drum Rotators Sheet: 9 of 9

Operation	Hazards Identified	Risk Assessment	Risk Control Measures in Place	Risk Control In Place (Date)
6. Storage of Attachment.	a) Attachment becoming damaged.	 Serious Risk to Pedestrians. Moderate Risk to Operator. 	 Regular Maintenance, inspection and testing according to the Instruction Manual to be carried out. Prior to storage, all dirt should be removed from the Drum Rotator and air-dried at the ambient temperature. Attachment to be stored in dry areas and away from any corrosive chemicals. 	m ruce (Dute)
	b) Attachment in the way of normal Workplace/Site Operations.	Moderate Risk to Pedestrians.	- Attachment to be stored in areas which will not interfere with the normal running of the Workplace/Site.	

Assessment carried out by:	Ben PRASAD, East West Engineering	Date of Assessment:	24 th February, 2015